

Leveraging IoT for Precision Health Monitoring in Livestock with Artificial Intelligence

Devinder Kaur

Sri Guru Granth Sahib World University, Mata Gujri College, Fatehgarh Sahib, India

Mata Gujri College, Fatehgarh Sahib, India

Amandeep Kaur Virk

Sri Guru Granth Sahib World University, Fatehgarh Sahib, India

1.1 INTRODUCTION

India, a densely populated nation, relies significantly on agriculture and dairy farming as a primary source of income, particularly within rural communities. The rapid population growth underscores the necessity for increased future food and dairy production. Historically, most Indian states have adhered to traditional livestock farming methods, with farmers making decisions based solely on their personal experience. However, contemporary trends are shifting away from these customary approaches as precision dairy technology gains prominence, propelling dairy farmers toward the realm of precision livestock farming. To make informed choices in livestock management, the availability of quantitative real-time data is crucial. This type of data is accessed and studied through the utilization of Information and Communication Technology (ICT), data analysis, machine learning (ML), and control systems [1].

Since humans rely on animals to meet their dairy product needs, it becomes crucial to uphold the well-being of these animals. Given that

certain diseases can be transmitted from animals to humans, the early prediction of cattle health and diseases holds significant importance [2]. However, the various facets associated with dairy farming, including milking, feeding, reproduction, and health, are frequently treated as distinct entities. As a result, ensuring a healthy life for each individual animal has become a formidable task. In the current era, innovation plays a pivotal role in healthcare systems. Among the domains experiencing significant advancements in recent years, electronic dairy farming stands out as particularly important [3]. Modern technologies, such as sensors, big data, and ML, present a fresh opportunity for farmers. Rather than reacting to diseases only when they become apparent, these technologies enable continuous monitoring of crucial animal well-being indicators, including movement, temperature, pulse rate, and humidity. Through the continuous data collection facilitated by sensors and the predictive capabilities of ML, farmers can now proactively identify, anticipate, and prevent cattle diseases prior to wide-scale outbreaks and the resulting catastrophic losses.

This kind of system offers a dual benefit to farmers. First, it enables a smaller number of farmers to efficiently manage a larger number of animals, leading to reduced production costs. Second, the system has the capability to notify farmers about potential diseases even before they reach the clinical stage. This early alert empowers farmers to take timely measures [4]. These innovative techniques applied in the dairy farming sector introduce novel approaches that can enhance and elevate future decision-making processes.

Despite the advancements in research, the practical application of these technologies has not been fully realized. Currently, veterinary doctors predominantly assess the physical parameters of animals through manual methods. Livestock farmers encounter significant challenges when it comes to monitoring cattle health. This underscores the critical necessity of translating theoretical knowledge into functional real-world systems.

1.2 CONCEPT OF PRECISION LIVESTOCK FARMING

Precision livestock farming (PLF) is a dynamic approach to monitoring that involves the continuous observation of animals through various

methods, such as behavior monitoring, analysis of milk constituents and yield, video analysis, record assessment, and physiological monitoring [5]. PLF involves continuous health monitoring of animals using methods like camera and image analysis, sound analysis, and sensors. These tools can be wearable, integrated with milking machines, stand-alone, or part of management software, all aimed at enhancing animal health in precision dairy technology [6].

The inception of PLF can be traced back to the introduction of individual electronic milk meters for dairy cows during the 1970s and early 1980s. This was followed by the implementation of behavior-based estrus detection, rumination tags, and real-time online milk analyzers [7]. Many of the pioneering developments in PLF originated in Europe, notably in countries like the United Kingdom, Belgium, Germany, Denmark, the Netherlands, Finland, and Israel [1].

PLF presents a promising avenue for achieving sustainable livestock production, necessitating collaboration across diverse research disciplines. The objective is to translate technological advancements into practical, actionable insights for farmers, equipping them to make well-informed choices [8].

Currently, PLF predominantly benefits larger animals, such as dairy cows, beef cattle, and horses, where the economic returns justify the investment in monitoring tags [7]. Dependable PLF solutions can elevate animal welfare and productivity, driving advancements in the field to the advantage of both livestock and their overall well-being [9]. As PLF technology becomes more cost-effective, its potential to provide additional value for stakeholders, especially farmers, becomes evident. It facilitates enhancements in animal welfare, health, efficiency, and environmental impact [10]. By combining hardware and intelligent software, valuable insights are extracted from diverse data sources, empowering farmers to improve animal health, well-being, yields, and environmental contributions [11]. One of the most important goals of PLF is to work on the well-being of animals [12]). Therefore, the PLF technologies offer the chance to further develop efficiency and recognize medical problems at the beginning phase.

These “smart technologies” designed to assist livestock farmers in monitoring animal well-being are currently a prominent subject of research. Numerous countries are already allocating significant resources to their development, with the aim of transitioning toward more sustainable practices in livestock farming.

1.3 IMPORTANCE OF MACHINE LEARNING IN PRECISION LIVESTOCK FARMING

Within dairy research, ML emerges as a promising technique with the potential to aid farmers in improving decision-making. ML algorithms possess the capacity to analyze integrated datasets, thereby facilitating holistic livestock management that encompasses essential influencing factors within the complex system of cattle, including cows [13]. By employing ML algorithms, it becomes feasible to predict the standard behavior of animals and issue alerts when observed behavior deviates from predefined thresholds.

In the domain of cattle husbandry, ML has been effectively employed to predict outcomes such as reproductive results, high somatic cell counts, and the onset of calving. The utilization of “big data” in farm animal medicine has expanded, and its conversion into “smart data” is gaining traction, enabling the maximization of existing data resources. Additionally, professionals currently invest substantial time in the analysis and interpretation of data to arrive at clinical diagnoses. While a human may require 30–60 minutes to comprehensively analyze all available data and identify ailments like mastitis, an ML system can accomplish this task within seconds. This rapid, straightforward diagnostic procedure can be performed frequently, leading to more consistent diagnostic reports [14]. ML algorithms can store category data and analyze enormous datasets that are difficult to evaluate using traditional statistical methods. As a result, statisticians claim that ML algorithms produce better results because they learn from the data presented, whereas traditional analysis methods are skewed by the researcher’s hypothesis [13].

Hence, ML holds significant potential as a valuable tool for PLF, aiding farmers in safeguarding the welfare of their animals.

1.4 LITERATURE REVIEW

In this section, we are going to present the literature review to explore the amalgamation of the Internet of Things (IoT) and ML in the domain of livestock farming. By analyzing a variety of scholarly works, this review aims to elucidate the current research landscape, advancements, and

applications at this innovative intersection. Our objective is to emphasize the significance of IoT and ML in enhancing livestock management, health monitoring, and productivity. Through this examination, we pinpoint emerging trends, challenges, and prospects in this evolving field, offering insights into potential avenues for future research and development.

Swain et al. [15] introduced a real-time application device that enables farmers to monitor and assess the present health metrics of cattle by comparing them against established healthy parameters, serving as a baseline to identify potential declines in animal well-being. The system utilized various sensors, including humidity and temperature sensors, pulse sensors, and rumination sensors, along with the Xbee module and Arduino 1.0.6 software. The outcomes were successful, achieving an accuracy rate of 72%–75% in detecting the health status of cows.

In a study conducted by Borchers et al. [16], automated activity, lying, and rumination monitors were employed to assess prepartum behavior and forecast calving in dairy cattle. The research evaluated the utility of ML approaches such as linear discriminant analysis, Random Forest, and neural networks in predicting calving. Through the utilization of neural network techniques, a combination of activity, rumination time, and lying behavior variables was analyzed, leading to the generation of precise and sensitive alerts.

Liakos et al. [17] presented a novel integrated computational analysis for predicting lameness in cattle using ML techniques. The study incorporated factors such as steps per day, total walking per day, lying duration per day, and eating frequency per day as contributing elements. The newly developed algorithm was tested on datasets containing both healthy and unhealthy cattle samples. The primary objective of utilizing these four features was to effectively distinguish and separate the samples. Among the ML methods employed, Random Forest yielded the most promising results.

Cowton et al. [18] devised and assessed a deep-learning approach employing Particle Swarm Optimization (PSO) to monitor the health of cattle. This methodology was specifically employed by leveraging environmental sensor data to enable the early identification of respiratory illness in developing pigs. An autoencoder model was constructed using two recurrent neural networks (RNNs). The results of the study highlighted that alterations in the environment could induce signs of respiratory illness in pigs within a remarkably short span of 1–7 days.

Kumari and Yadav [19] employed a Raspberry Pi 3 model as a central controller to investigate crucial indicators affecting cattle health, including

body temperature, heart rate, and rumination. Through the utilization of IoT, a cloud-based database was established, enabling the captured data to be accessible online from any location. This data could be accessed by a farmer or dairy owner using an Android application on their smartphone, or alternatively, they could receive an email notification for easy access to monitor their animals' health.

Pratama et al. [20] proposed the development of a collar device capable of capturing body temperature, heart rate, and movement of cattle. In addition, they designed a base station for local server management and a web application to display data, facilitating the analysis of cattle health issues. To classify health outputs into normal, slightly abnormal, and severely abnormal categories using data collected from the sensors, ML algorithms were employed.

Benjamin and Yik [21] elucidated various ML algorithms, provided a comprehensive overview of existing literature, and deliberated on the potential applications of these technologies for enhancing pig health. Their focus centered on essential sensors and sensor network systems that could contribute to advancements in this area. Vyas et al. [22] used the IoT to detect foot and mouth illness and mastitis in cows. ML techniques were used to detect these disorders using a range of sensors to distinguish numerous factors in animals, such as temperature, motion, and sound.

Xu et al. [23] aimed to investigate the feasibility of clustering the metabolic status of individual cows in early lactation based on plasma values. They also evaluated the effectiveness of ML algorithms in predicting metabolic status using on-farm cow data. The study analyzed eight commonly used ML algorithms, including K-Nearest Neighbor, Support Vector Machine, Decision Tree, Naive Bayes, Bayesian Network, Artificial Neural Network (ANN), Bootstrap Aggregation, and Random Forest. From their analysis, the two most successful algorithms in predicting metabolic status using on-farm data were the Support Vector Machine and Random Forest.

Chaudhry et al. [2] conducted a study that involved contrasting the features offered by various systems alongside their constraints. The research also encompassed an evaluation of existing technology-driven solutions and the associated equipment. Furthermore, the study introduced a real-time animal health monitoring system grounded in the IoT. Garcia et al. [24] conducted a systematic literature review that focused on the recent progress in utilizing ML within the context of PLF, with a specific emphasis on grazing practices and animal health. The review underscored the potential applications of ML in the livestock industry, outlined the

prevailing sensors, software, and data analysis techniques, and expounded upon the growing accessibility of diverse data sources.

Wagner et al. [25] conducted research exploring the application of ML for the identification of abnormal behavior through continuous monitoring, utilizing a ruminal bolus to measure pH and predict occurrences of Subacute Ruminal Acidosis (SARA) in cows. In their study, they employed ML techniques, including Decision Tree for Regression (DTR), Multilayer Perceptron (MLP), K-Nearest Neighbors for Regression (KNNR), and Long Short-Term Memory (LSTM). The results indicated that KNNR achieved the highest performance, successfully detecting 83% of SARA incidents.

Unold et al. [26] introduced a Cow Health Monitoring System focused on categorizing the behavior of dairy cows, specifically targeting estrus detection. The study employed a Cow Health Monitoring System composed of hardware components, a cloud system, and an end-user application. Using classification tree analysis, significant features were identified, and the C4.5 decision tree learning algorithm was applied to detect essential behaviors of dairy cows. The developed system demonstrated effectiveness and precision in monitoring dairy cow behavior to identify specific physiological states like estrus or health issues such as mastitis.

Contla Hernández et al. [27] employed mid-infrared (MIR) spectrometry to analyze the content of cow milk. The research explored the feasibility of identifying cow illnesses using Random Forest, Support Vector Machine, Convolutional Neural Network, Neural Network, and ensemble models. The outcomes revealed that employing a neural network yielded a satisfactory level of accuracy in detecting health concerns.

Suseendran and Balaganesh [28] developed a Smart Cattle Health Monitoring System utilizing IoT sensors to effectively anticipate cattle diseases ahead of time. In order to ensure dependable data transmission between the gateway and cow collar, the study introduced a health monitoring module based on fuzzy logic. The system they proposed demonstrated superior performance compared to existing systems, exhibiting a 4% improvement in packet delivery ratio, a 12% enhancement in residual energy, and a 14% reduction in latency, as indicated by the experimental data.

As the domain of cattle health monitoring systems based on IoT continues to garner attention, a consolidated overview of pertinent research papers becomes crucial. In an effort to distill the advancements, methodologies, and findings in this field, a tabular summary of key research works has been curated in Table 1.1 [29]. This tabular exposition not only

TABLE 1.1

Summary of Research Papers on the Application of IoT for Livestock Health Monitoring

References	Objective of the Study	Parameters Observed	Hardware Used	Observations
Swain et al. [15]	To present a device to monitor the health parameters of the cattle to spot any deterioration in the cattle's health	Heart rate, temperature, rumination, and body humidity	Arduino NANO, Xbee module, and a combination of sensors	Accuracy (72%–75%) is not as high because of the simplicity of the developed system.
Benjamin and Yik [21]	To introduce ML algorithms and literature on relevant sensors drawing from industry pig welfare audit criteria and explain how these applications can be used to improve swine welfare	Sound, heat, and motion	Remote sensors such as cameras, microphones, thermometers, and accelerometers	PLF can provide producers with information about the welfare of the whole herd as well as individual animals by collecting and analyzing vast quantities of data.
Eckelkamp [5]	To present the role of wearable precision dairy technologies (WPDT) in the detection of lameness, mastitis, metabolic disorders, and metritis	Feed bunk, rumination time, eating time, lying time, standing time, walking time, activity, lying-to-standing transitions, temperature, and rumen pH	Wearable precision technologies such as neck collars, torso bands, and leg tags	A number of wearable technologies are available to detect diseases in animals, but stronger sensitivity and specificity are needed.
Pratama et al. [20]	To produce normal, less normal, and abnormal health classification outputs based on data collected using sensors and classified using ML	Body temperature, heart rate, and movement	Collar device to read body temperature, heart rate sensor, and motion sensor, Raspberry Pi, a base station for local server management and web application to visualize data and analytic health conditions	The prediction system that is made can make the health of the heart rate and body temperature to be normal, which is less normal and abnormal, with an accuracy of 84% Support Vector Machine (SVM) and using Decision Tree (DT) and 91% accuracy.

Priya and Jayaram [3]	To describe unique sensors that are associated with wireless sensor networks to monitor the health status of cattle	Temperature, motion and heart rate	Sensor modules, RL78, GSM, and Android application	A framework to monitor an animal's health has been proposed.
Vyas et al. [22]	To reflect on the detection of foot and mouth disease and mastitis disease in cows using of things (IoT)	Temperature, motion, sound, etc.	Rumination sensor, motion sensor, temperature sensor, and Raspberry Pi3 controller	Use of the IoT in the detection of mastitis and FMD reduces the lousy quality of milk and infertility among cows.
Chaudhry et al. [2]	To review the existing technology-based solutions and related equipment and provide a comparison of the features offered by these systems and their limitations	Skin temperature, rumination time, and heart rate its variability	IoT-based sensor unit to measure various health-related parameters	ML can be applied to detect lameness in cattle, Linear Regression Model to predict milk yield, and computer vision and deep learning can be used to analyze health factors.
Unold et al. [26]	To present an IoT-based livestock monitoring system to automate the measurement of dairy cow health state	Feeding, ruminating, resting, and movement	Cow device consisting of sensors, the hub, Wi-Fi access points, and routers, database, and application server	Accurately monitors the behavior of the dairy cows and detects some health problems (e.g., mastitis, estrus).
Neethirajan [4]	To explore the role of sensors, big data, artificial intelligence (AI) and ML to lower production costs, increase efficiencies, enhance animal welfare	Voice signals of animals, visual data of various animal movements, and other such animal behavior data	Hardware sensors such as camera or vision sensors, infrared thermal imaging sensors, temperature sensors, RFID tags, accelerometers, motion sensors, pedometers, facial recognition machine vision sensors, and microphones	Advanced AI and ML algorithms can be applied for the detection of diseases and the monitoring of animals.
Suseendran and Balaganesh [28]	To accurately predict the illness of cattle using a fuzzy-based Smart Cattle Health Monitoring System employing IoT sensors	Heartbeat, body temperature, pulse rate, rumination, and respiration information	Sensors, Wi-Fi module, Arduino	The proposed system achieves a 4% higher packet delivery ratio, 14% lesser delay, and 12% higher residual energy as compared to the existing systems.

underscores the spectrum of perspectives but also elucidates the evolving landscape of IoT-enabled cattle health monitoring.

In summation, the tabular summary presented in Table 1.1 encapsulates a diverse array of research papers integral to the realm of cattle health monitoring systems based on IoT. This compilation not only accentuates the breadth of research methodologies employed but also underscores the pivotal role of IoT technology in modern livestock farming. The amalgamation of these insights not only enriches our comprehension of IoT applications in cattle health but also lays a foundation for more nuanced inquiries into this burgeoning field.

1.5 RESEARCH GAPS

The literature review has uncovered the following research gap within the current systems:

- i. *Farmers' Lack of Awareness about Diseased Cattle*: Due to the absence of timely notifications regarding unusual changes in cattle health, farmers often remain unaware of any potential afflictions. This lack of awareness hinders their ability to administer timely treatment, potentially exacerbating the severity of diseases.
- ii. *Need for Comprehensive Datasets*: Another notable research gap pertains to the demand for substantial datasets. The utilization of ML techniques for data prediction across various aspects of dairy farming has been observed in existing systems. However, the accuracy of the generated algorithms is contingent upon the availability of extensive, integrated datasets. By analyzing sizable, comprehensive datasets, it is conceivable to enhance decision support systems for farmers, thereby enabling them to advance the welfare and productivity of their livestock.
- iii. *Enhancement of ML Algorithm Classification Performance*: A significant research gap pertains to the need for enhancing the classification performance of ML algorithms. Commercially available sensors capable of tracking the health and physiology of dairy cows are in existence. However, there exists ambiguity regarding the effectiveness of the decision support derived from these sensors due to the limited availability of research focusing on the efficacy of the underlying algorithms. This underscores the challenge of improving and

predicting the categorization performance of algorithms within the realm of PLF. While the potential of ML has been widely acknowledged by researchers, it remains crucial to collaboratively employ these potent tools alongside data scientists and the dairy industry to comprehensively grasp their true significance.

1.6 COMPARATIVE ANALYSIS

Within the domain of IoT-based cattle health monitoring systems, a diverse array of research studies has surfaced, each contributing its own unique insights and advancements. To distill this wealth of knowledge and provide a structured assessment of these studies, we present a comprehensive comparative analysis. The purpose of this analysis is to offer readers a systematic overview of key research papers, shedding light on their individual strengths and limitations in the quest to enhance cattle health through IoT technology. Our aim is to synthesize these findings, helping readers gain a deeper understanding of the evolving landscape of IoT-enabled cattle health monitoring and identifying promising avenues for future research and development. In Table 1.2, we present a tabular summary of these research works for the convenience of reference and evaluation.

1.7 FUTURE RESEARCH DIRECTIONS

Following the aforementioned comprehensive literature review, it is evident that the landscape of IoT-based cattle health monitoring systems offers immense potential while also revealing areas that require further exploration and innovation. This section delineates the future research directions within the domain of IoT-based cattle health monitoring systems.

- i. *Integration of Cutting-Edge Sensors:* One promising avenue for future research entails the incorporation of advanced sensors and technologies to elevate the precision and breadth of data collection related to cattle health. Delving into the integration of wearable devices, smart collars, and ingestible sensors holds the promise of a more holistic understanding of individual animal health.

TABLE 1.2

Comparative Analysis of Research Papers on IoT-Based Livestock Health Monitoring Systems

Research Paper	Strengths	Weaknesses
Swain et al. [15]	• Comprehensive sensor usage (humidity, temperature, pulse, rumination) • Achieved 72%–75% accuracy in detecting cow health	• Use of older software (Arduino 1.0.6) • Limited exploration of ML techniques
Borchers et al. [16]	• Automated activity, lying, rumination monitors • Explored ML (linear discriminant analysis, Random Forest, neural networks)	• Primarily focused on calving prediction • Limited discussion on data accessibility and management
Liakos et al. [17]	• Holistic approach with various health indicators • Promising results with Random Forest	• Predominantly focused on lameness prediction • Limited discussion on real-time data processing and data accessibility
Cowton et al. [18]	• Utilized deep learning for respiratory illness detection • Rapid response, detecting illness within 1–7 days	• Focused only on pigs • Lack of emphasis on data accessibility and management
Kumari and Yadav [19]	• Cloud-based database for remote data access • Investigated key cattle health indicators	• Limited discussion on ML for data analysis • Scalability impacted by Raspberry Pi 3 as the central controller
Pratama et al. [20]	• Collar devices and ML for health classification • Web application for data display and analysis	• Lack of details on ML techniques and accuracy rates • Limited exploration of sensor types
Benjamin and Yik [21]	• Comprehensive literature review on pig health with IoT • Discussed potential applications for enhancing animal health	• No original research or experiments conducted • No focus on specific sensor technologies or ML techniques
Vyas et al. [22]	• Real-world applications with IoT for disease detection in cows • Use of ML for disorder detection	• Limited discussion on data management and accessibility • Focus primarily on specific diseases, potentially missing broader health monitoring applications

- ii. *Predictive Analytics and ML*: The development and application of ML algorithms for predictive analytics in cattle health monitoring represent a pivotal direction. Leveraging historical data, these algorithms can forecast health issues, enabling proactive intervention. However, refining these models to improve accuracy and adaptability across diverse cattle breeds and environmental conditions remains a significant challenge demanding attention.
- iii. *Scalability and Cost-Effectiveness*: Scalability remains a paramount concern, especially for small-scale farmers. The future trajectory of research should focus on exploring cost-effective solutions that can be seamlessly adopted across diverse farming operations. This may encompass the investigation of low-cost sensor alternatives, efficient communication protocols, or cloud-based solutions accommodating varying resource constraints.
- iv. *User-Friendly Interfaces and Mobile Applications*: User adoption and engagement are pivotal for the success of IoT-based cattle health monitoring systems. The research landscape should prioritize enhancements in user interfaces and the development of mobile applications that facilitate remote monitoring and data management. These efforts aim to render the system accessible and user-friendly for farmers and veterinarians.

In conclusion, the future directions signify opportunities to advance the domain of IoT-based cattle health monitoring systems. Exploring these research domains will not only contribute to livestock welfare and the sustainability of cattle farming practices but also foster the integration of state-of-the-art technology into agriculture, rendering the industry more efficient and productive.

1.8 DISCUSSIONS

Through a comprehensive review of prior research endeavors in this domain, it has become evident that there is a pressing need for an automated system capable of real-time monitoring of animal health. To address this need, we propose an IoT-based solution model aimed at detecting diseases in cows within the context of PLF. This proposed system is designed to offer dairy farmers timely alerts or notifications concerning cow diseases,

facilitated by the collection of behavioral data through real-time sensor monitoring. This proactive approach not only aids in averting disease outbreaks but also minimizes potential losses incurred as a result.

To effectively employ mechanistic models in dairy farming, the acquisition of extensive and diverse datasets becomes essential. These datasets can be efficiently gathered through the utilization of various sensors. Predicting diseases in dairy cows can be achieved by implementing an IoT-based hardware device and leveraging ML algorithms to discern the health status of the cows. The ensuing steps required for this process are succinctly outlined as follows:

- i. *Data Collection Using Sensors*: Real-time data from animals, such as cows, is collected using an array of hardware sensors. These sensors include accelerometers, motion sensors, pulse rate sensors, temperature sensors, and microphones. This diverse set of sensors helps gather comprehensive information about the animals' behavior, movement, health indicators, and environmental conditions.
- ii. *Data Transmission to Raspberry Pi*: The data collected by the sensors is then transmitted to a Raspberry Pi microcontroller. This microcontroller is equipped with a built-in Wi-Fi module that enables the transfer of the sensed data to a cloud-based platform or a designated server for further analysis.
- iii. *Advanced ML Analysis*: The broad dataset obtained from the sensors is then subjected to analysis using advanced ML algorithms. These algorithms leverage the collected information to analyze, predict, and provide alerts to farmers in case any abnormalities or unusual patterns are detected. The algorithms can perform tasks like clustering, classification, and pattern recognition, which are crucial for monitoring and identifying potential diseases in animals through sophisticated data analysis techniques.
- iv. *Alerts via Mobile App*: The determined health status of the cows is communicated to the farmer through alerts sent via a dedicated mobile application. These alerts inform the farmer about the detected conditions of the cows, allowing for timely intervention and necessary actions to ensure animal welfare.

In essence, this process involves the integration of sensors, data transmission, advanced ML, and real-time alerts to empower farmers with the means to proactively manage their livestock's health and well-being.




FIGURE 1.1

Proposed system architecture to predict diseases in dairy cows.

As a result, when it comes to cattle farming, sensors, big data, advanced AI, and ML are all intertwined to provide a comprehensive solution.

Figure 1.1 diagrammatically represents the proposed system architecture.

1.9 CONCLUSION

Based on an analysis of existing research on disease detection in livestock, several key conclusions can be drawn. First, cattle are susceptible to a variety of diseases. Unfortunately, the absence of notifications when abnormal health variations occur means that farmers remain unaware of potential illnesses affecting their cattle. Consequently, farmers may not provide timely treatment, leading to the potential exacerbation of disease severity. Examining the landscape of current systems reveals that ML methodologies exhibit predictive capabilities across various domains within dairy farming. However, the reliability of these algorithms hinges on the availability of extensive integrated datasets. The potential for farmers to enhance their decision support systems through the analysis of these comprehensive datasets could greatly improve the well-being and efficiency of their livestock. The availability of commercial sensors designed to monitor dairy cow physiology and health indicators is noteworthy. Nonetheless, the efficacy of the decision assistance provided by these sensors remains unclear due to the scarcity of published data concerning the

underlying algorithmic performance. A significant challenge pertains to the imperative of forecasting and enhancing the performance of algorithms used within PLF. Despite widespread recognition of the potential of ML, it is essential to collaboratively implement these powerful tools in collaboration with dairy farmers and data scientists to fully unlock their advantages. This collective effort is crucial to fully realizing the potential benefits of these innovative approaches.

REFERENCES

- 1 Banhazi, T. M., Lehr, H., Black, J. L., Crabtree, H., Schofield, P., Tschärke, M., & Berckmans, D. (2012). Precision livestock farming: an international review of scientific and commercial aspects. *International Journal of Agricultural and Biological Engineering*, 5(3), 1–9.
- 2 Chaudhry, A. A., Mumtaz, R., Zaidi, S. M. H., Tahir, M. A., & School, S. H. M. (2020, December). Internet of Things (IoT) and machine learning (ML) enabled livestock monitoring. In *2020 IEEE 17th International Conference on Smart Communities: Improving Quality of Life Using ICT, IoT and AI (HONET)* (pp. 151–155). IEEE.
- 3 Priya, M. K., & Jayaram, B. G. (2019). WSN-based electronic livestock of dairy cattle and physical parameters monitoring. In *Emerging Research in Electronics, Computer Science and Technology* (pp. 37–45). Springer, Singapore.
- 4 Neethirajan, S. (2020). The role of sensors, big data and machine learning in modern animal farming. *Sensing and Bio-Sensing Research*, 37, 100367.
- 5 Eckelkamp, E. A. (2019). Invited review: current state of wearable precision dairy technologies in disease detection. *Applied Animal Science*, 35(2), 209–220.
- 6 Bewley, J. M., Borchers, M. R., Dolecheck, K. A., Lee, A. R., Stone, A. E., & Truman, C. M. (2017). Precision dairy monitoring technology implementation opportunities and challenges. *Large Dairy Herd Management*, 3, 1251–1264.
- 7 Halachmi, I., Guarino, M., Bewley, J., & Pastell, M. (2019). Smart animal agriculture: application of real-time sensors to improve animal well-being and production. *Annual Review of Animal Biosciences*, 7, 403–425.
- 8 Vranken, E., & Berckmans, D. (2017). Precision livestock farming for pigs. *Animal Frontiers*, 7(1), 32–37.
- 9 Berckmans, D. (2017). General introduction to precision livestock farming. *Animal Frontiers*, 7(1), 6–11.
- 10 Schillings, J., Bennett, R., & Rose, D. C. (2021). Exploring the potential of precision livestock farming technologies to help address farm animal welfare. *Frontiers in Animal Science*, 2.
- 11 Berckmans, D. (2014). Precision livestock farming technologies for welfare management in intensive livestock systems. *Revue scientifique et technique*, 33(1), 189–196.
- 12 Pomar, J., López, V., & Pomar, C. (2011). Agent-based simulation framework for virtual prototyping of advanced livestock precision feeding systems. *Computers and Electronics in Agriculture*, 78(1), 88–97.

- 13 Cockburn, M. (2020). Application and prospective discussion of machine learning for the management of dairy farms. *Animals*, 10(9), 1690.
- 14 Hyde, R. M., Down, P. M., Bradley, A. J., Breen, J. E., Hudson, C., Leach, K. A., & Green, M. J. (2020). Automated prediction of mastitis infection patterns in dairy herds using machine learning. *Scientific Reports*, 10(1), 1–8.
- 15 Swain, K. B., Mahato, S., Patro, M., & Pattnayak, S. K. (2017, May). Cattle health monitoring system using Arduino and LabVIEW for early detection of diseases. In *2017 Third International Conference on Sensing, Signal Processing and Security (ICSSS)* (pp. 79–82). IEEE.
- 16 Borchers, M. R., Chang, Y. M., Proudfoot, K. L., Wadsworth, B. A., Stone, A. E., & Bewley, J. M. (2017). Machine-learning-based calving prediction from activity, lying, and ruminating behaviors in dairy cattle. *Journal of Dairy Science*, 100(7), 5664–5674.
- 17 Liakos, K., Moustakidis, S. P., Tsiotra, G., Bartzanas, T., Bochtis, D., & Parisses, C. (2017). Machine Learning based computational analysis method for cattle lameness prediction. In *HAICTA* (pp. 128–139).
- 18 Cowton, J., Kyriazakis, I., Plötz, T., & Bacardit, J. (2018). A combined deep learning gru-autoencoder for the early detection of respiratory disease in pigs using multiple environmental sensors. *Sensors*, 18(8), 2521.
- 19 Kumari, S., & Yadav, S. K. (2018). Development of IoT based smart animal health monitoring system using Raspberry Pi. *International Journal of Advanced Studies of Scientific Research*, 3(8), 24–31.
- 20 Pratama, Y. P., Basuki, D. K., Sukaridhoto, S., Yusuf, A. A., Yulianus, H., Faruq, F., & Putra, F. B. (2019, September). Designing of a smart collar for dairy cow behavior monitoring with application monitoring in microservices and internet of things-based systems. In *2019 International Electronics Symposium (IES)* (pp. 527–533). IEEE.
- 21 Benjamin, M., & Yik, S. (2019). Precision livestock farming in swine welfare: a review for swine practitioners. *Animals*, 9(4), 133.
- 22 Vyas, S., Shukla, V., & Doshi, N. (2019). FMD and mastitis disease detection in cows using Internet of Things (IoT). *Procedia Computer Science*, 160, 728–733.
- 23 Xu, W., van Kneusel, A. T., Vervoort, J. J., Bruckmaier, R. M., van Hoeij, R. J., Kemp, B., & Saccenti, E. (2019). Prediction of metabolic status of dairy cows in early lactation with on-farm cow data and machine learning algorithms. *Journal of Dairy Science*, 102(11), 10186–10201.
- 24 Garcia, R., Aguilar, J., Toro, M., Pinto, A., & Rodriguez, P. (2020). A systematic literature review on the use of machine learning in precision livestock farming. *Computers and Electronics in Agriculture*, 179, 105826.
- 25 Wagner, N., Antoine, V., Mialon, M. M., Lardy, R., Silberberg, M., Koko, J., & Veissier, I. (2020). Machine learning to detect behavioural anomalies in dairy cows under sub-acute ruminal acidosis. *Computers and Electronics in Agriculture*, 170, 105233.
- 26 Unold, O., Nikodem, M., Piasecki, M., Szyk, K., Maciejewski, H., Bawiec, M., ... & Zdunek, M. (2020, June). IoT-based cow health monitoring system. In *International Conference on Computational Science* (pp. 344–356). Springer, Cham.
- 27 Contla Hernández, B., Lopez-Villalobos, N., & Vignes, M. (2021). Identifying health status in grazing dairy cows from milk mid-infrared spectroscopy by using machine learning methods. *Animals*, 11(8), 2154.

- 28 Suseendran, G., & Balaganesh, D. (2021). Smart cattle health monitoring system using IoT sensors. *Materials Today: Proceedings*.
- 29 Kaur, D., & Kaur, A. (2022). IoT and machine learning-based systems for predicting cattle health status for precision livestock farming. In *2022 International Conference on Smart Generation Computing, Communication and Networking (SMART GENCON)* (pp. 1–5). IEEE.